Amendment One GBNERR Savanna Boardwalk Replacement - 3160007842

February 13 2025

Mississippi Department of Marine Resources

To: Prospective Bidders

RE: Questions and Answers and Bid Form Bid Schedule - Base Bid Edit

1)-Will FRP decking panels be allowed for a substitute vs Thruflow decking?

Yes, FRP is allowed.

2)-If the FRP decking material is used, there will need to be a redesign of the handicap rail. Otherwise, you would be trying to lag into the top of 2" r/c material that could create a problem with splintering of the r/c material.

See revised Scope below (number 5). We will allow the contractor to use their best judgement based on the material used.

3)-Will builders risk insurance be required?

Only the insurance requirements stated in the IFB are necessary.

Bid Form Bid Schedule - Base Bid Edit

The Base Bid section is changed as follows:

All labor, materials, equipment, mobilization, and demobilization pertaining to the procurement and execution of the scope of work as shown and specified within the contract documents.

1. Demolition and removal of existing 1014' decking and stringers and installation of new material to span 1024’ ;
2. Installation of new 2" x 6" 2.5 CCA treated stringers (4) @ 15 O.C. per 10' bent, outside stringers lagged to pilings with 3/8 x 6" HDG lags and CCA treated headers as needed;
3. Install new FRP deck panels or approved equivalent;
4. Decking screwed down with the appropriate fasteners and hardware;
5. Install new 4"x4" or approved equivalent, wheelchair bumper, bumpers secured using appropriate lag screws/hardware and riser blocks as necessary.